

Grattan Healy BEmech MBA, Ierne Ltd IRENEC 2013 Türkan Saylan Kültür Merkezi, Maltepe, Istanbul Friday 28th June 2013

..... IRENEC 3rd INTERNATIONAL 100% RENEWABLE ENERGY CONFERENCE

Contents

Resource in Ireland
Accessing Resource

Issues with Access


- Operation of Electricity System
- -Access to Electricity Network
- -Legal issues for grid
- Other obstacles


Conclusions



Hywind (Statoil/Siemens)









Estimate of Ireland's technical resource, electricity:

Onshore wind: 2,000 TWhrs/yr


Offshore wind, fixed/floating: 7,000 TWbrs/yr

Approximate demand:

Ireland 25 TWhrs per year

UK 350 TWhrs per year


EU 3,000 TWhrs per year




Historical trend in Ireland

- First thermal power station 1947 (North Wall)
- Up to then virtually all electricity from hydro: Ardnacrusha 86MW (1929-34) Liffey 38MW (1938)
- High % energy in Ireland then from renewables (but limited data publicly available at present)
- Renewables only 6% of TPER in 2011









- •UK-Ireland MOU signed 24th January 2013
- •IGA being negotiated for year end/early 2014
- •Would enable trade between the countries under RE Directive
- •Supports paid & credits claimed by the UK
- •UK wants up to 10,000 MW by 2020
- Main issues are price and delivery by 2020

..... (IRENEC) 3rd INTERNATIONAL 100% RENEWABLE ENERGY CONFERENCE


Current development scale


- •Onshore connected: ~ 1,800 MW
- •Onshore contracted: ~1,600 MW
- •Offshore connected: 25 MW
- •Onshore in development: 10,000 MW
- •Offshore consented: 2,000 MW
- Offshore in development: 5,000MW
- •Potential output per year: 60 TWbrs

IRENEC 3rd INTERNATIONAL 100% RENEWABLE












Operation of electrical system •RE electricity target 40% both North & South •Implies instantaneous -75% on all-island system •Highest non-synchronous penetration in EU •TSO considers this at limits of dynamic stability •Requires a set of measures to enable 75% (DS3) •Limit of 50% currently operating •MinGen' also imposing limit of around 40% •Resulting in significant curtailment of free energy












Table 1. Estimated risk & cost in 'forward' & 'backward' renewable development models

	Approx. probability	Approximate timing	Rough cost estimate				
Backward development model							
Get into a Gate	50%	3 yrs	€7k + €20-80k				
Get grid offer	100%	3-6 yrs	€300k/MW				
Get planning	30%	1-5 yrs	€250k+				
Get REFIT	50%	1-2 yrs	€0				
Get Finance	70%	1-2 yrs	€100-200k				
Overall	5%	15-20 yrs	€1 million +				
Forward development model							
Get planning	30%	1-5 yrs	€250k+				
Get grid offer	100%	0.5 yrs	€7k + €20-80k				
Get grid	100%	3 yrs	€50k/MW				
Get REFIT	100%	0 yrs	€0				
Get finance	90%	1 yr	€100k				
Overall	27%	5-8 yrs	€ half million				


Forward & Backward model risks/costs



Legal issues for grid

- Article 16 of 2009 RE Directive requires:
 - Priority dispatch
 - Guaranteed transmission
 - & either priority or guaranteed access
- Ireland elected for priority access (NREAP)
- SEMC delivered priority dispatch, ignoring cost
- But faster access for fossil due to 'security of supply'
- Uncompensated unquantified curtailment instead of adequate measures to avoid it
- Excuse is 'Safety & reliability' wrong interpretation








Table 2. Estimated effect of paying for constraint & grid, using author's proprietary financial model

			Constraint & Curtailment	Underground Cable	
10MW project; constant 20		Existing	paid at	Connection	
year Equity IRR	Units	model	REFIT	paid	Both
REFIT start price (unadjusted)	€c/kWhr	6.808	6.808	6.808	6.808
REFIT start price (adjusted)	€c/kWhr	6.808	6.121	5.794	5.224
CAPEX	€m	14.35	14.35	11.74	11.74
Annualised interest rate (4 loan					
payments/yr)	%	6.00%	5.50%	6.00%	5.50%
Gearing	%	80.00%	85.00%	80.00%	85.00%
Unpaid constraint & curtailment	%	6-9%	0	6-9%	0
Average annual paid production	MWhr/yr	26,961	29,290	26,961	29,290
20 yr Equity IRR (unadjusted)	%	10.61	16.88	19.53	29.63
20 year Equity IRR (adjusted)	%	10.61	10.61	10.61	10.61
PSO cost (incl. 0.5c balancing;					
SMP at 5.8c)	€/yr	406,580	240,472	133,190	0
Connection cost to consumer,					
financed ESB at 4% over 50 yrs	€/yr	0	0	121435	121435
Consumer cost, PSO + connect.	€/yr	406580	240472	254625	121435

Current approach to support is economically inefficient

..... IRENEC 3rd INTERNATIONAL 100% RENEWABLE ENERGY CONFERENCE

Conclusions

- Ireland has a truly enormous renewable energy resource
- But difficulty with 2020 targets, and can't go beyond
- Without solution to achieve targets, not able to export
- Isolated grid a problem for large volumes variable RE
- Ireland identifying significant issues before many others
- High risk and cost with backward development model
- No possibility of '100% Renewables' with this approach
- Significant AC interconnection NI-Scotland a solution

··(IRENEC)······ 3rd INTERNATIONAL 100% RENEWABLE



- Huge connection delays and costs a significant problem
- Uncompensated curtailment a major problem
- Approach highly economically inefficient
- More economically efficient for:
 grid owner to fund grid connections
 supports to be paid on available output
 connections to have time limits, employ forward model
- •Legally required to take measures to enable renewables
- Need all these changes to approach '100% Renewables'

